



OIS plc - Southern

21 Charlton Drive, Corngreaves Trading Est.,
Cradley Heath, Warley, W.Midlands. B64 7BJ
United Kingdom

Tel:(0384)64021 Fax:(0384) 638281 Telex:33584

i getting it right

Report No : MID 9308086
Works Order No : 931091
Customer : Presco Scaffolding Ltd
Customer O/No : Verbal (P. Jones)
Date Tested : 13/08/93
Date Reported : 16/08/93

INTRODUCTION

One off Putlog Coupler, with a zinc and yellow passivated finish and stamped "presco UK""G3" was submitted for testing.

METHOD

The Coupler was stressed as per BS 1139, Part 2, 1982, the bolt being torqued up to 45lb.ft.

RESULTS

The Coupler withstood a load of 0.12 Tonf (1.2 kN) without slipping.

CONCLUSION

The Coupler conforms to BS 1139, Part 2, 1982.

Yours faithfully,
for OIS Plc

Trevor W Deakin

T.W. DEAKIN
Senior Metallurgist



No.0074 (N)



No. 0074(N)

